

SITE : MATERIAL STORES / OFFICE ON GROUND FLOOR & OFFICE / SERVICE AREA ON FIRST FLOOR R.D.P.L. ROAD NO. 12, V.K.I.A. JAIPUR					
Sr.No	Item Description	Quantity	Unit	Rate	Amount (Rs)
UPTO PLINTH & D.P.C. LEVEL					
1	SITE CLEARENCE & CHIESLING OF STONE PILLARS OF EXISTING BUILDING PROJECTING OUT				
	Total Amount Rs.		L.S.		
2	EARTH WORK				
(a)	Earth work in excavation by mechanical means (Hydraulic Excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering / ramming and disposal of surplus excavated soil as directed with in a lead of 100 meter.In All kinds of soil	535.42	cu.m		
(b)	Filling in plinth with excavated surplus sand under floor including watering / ramming / consolidating & dressing complete in all respect. excluding cost of sand.	631.57	cu.m		
(c)	Supplying & Filling in plinth with river sand under floor including watering ,ramming ,consolidating & dressing complete in all respect. including cost of sand.	549.6	cu.m		
	Total Amount Rs.				
3	PCC				
	Providing and laying in position cement concrete including curing, compaction with vibrator etc. excluding the cost of centering / shuttering & reinforcement in 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	57.21	cu.m		
	Total Amount Rs.				
4	SHUTTERING WORK-				
(a)	Centerring & shuttering with plywood or steel plates including strutting, propping bracing both ways and removal of formwork for foundation rafts,footings,strap beams, columns, dpc beam sides etc. upto dpc level..	168.21	sq.m		
(b)	Centering & shuttering with plywood or steel sheets including strutting, propping bracing both ways with steel props and removal of formwork for upto floor five level for :Suspended floors, roofs, landings, staircases, balconies, girders, cantilevers, bands, coping bed plates, anchor blocks, sills, chhajjas, lintel, beam, plinth beam etc.	206.00	sq.m		
(c)	Centering & shuttering with plywood or steel sheets including strutting, propping bracing both ways with steel props and removal of formwork for Columns.	60.45	sq.m		
	Total Amount Rs.				
5	REINFORCEMENT				
	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) complete in all respect.	10796.36	KG		
	Total Amount Rs.				
6	CEMENT CONCRETE WORK IN FOUNDATION / COLUMNS / D.P.C.				

(a)	Providing & laying in position specified grade of reinforced cement concrete including curing,compaction with vibrator,finishing with rendering in cement, sand mortar,1:3,(1 Cement :3 Coarse sand) excluding the cost of centering / shuttering & reinforcement. All works upto dpc level.:1:1:2(1 cement; 1:coarse sand; 2 graded stone aggregate 20 mm nominal size) ,Or M-25 Nominal mix.in foundations.	108.18	cu.m		
(b)	Providing & laying in position specified grade of reinforced cement concrete including curing,compaction,finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) excluding the cost of centering / shuttering & reinforcement.1:1:2 (1 cement :1 coarse sand :2 graded stone aggregate 20 mm nominal size) Or M-25 Nominal mix in columns.	6.27	cu.m		
(c)	Providing & laying in position specified grade of reinforced cement concrete including curing compaction,finishing with rendering in cement sand mortar 1:3(1 cement :3 coarse sand),excluding the cost of centering / shuttering & reinforcement.:with 1:1.5:3 (1 cement: 1.5 coarse sand :3 graded stones aggregate 20 mm nominal size) Or M-20 Nominal mix in D.P.C beams.	17.72	cu.m		
Total Amount Rs.					
7	SOLING & P.C.C. UNDER FLOORS				
(a)	Providing & doing 150mm thick stone soling ,under the floors with 150 mm nominal size crushed stone having average size of 150 mm(Non BSR Item)	183.21	cu.m		
(b)	Providing & doing 75mm thick P.C.C. M-10 grade nominal mix 1:3:6 (1 cement : 3 coarse sand :6 graded stone aggregate 20mm nominal size) over 150 mm thick soling	91.60	cu.m		
Total Amount Rs.					
8	SUB STRUCTURE MASONRY				
	Random Rubble stone masonry with hard stone in foundation upto plinth (above 30 CM thick walls) in: Cement sand Mortar 1:6 (1-Cement : 6 coarse sand) including curing.	225.28	cu.m		
Total Amount Rs.					
9	ANTITERMITE TREATMENT -				
	Providing and injection chlopyrifous emulsifiable concrete 20% with 1% concentration for pre constructional anti termite treatment as per IS:6313,part-3rd,as ammended from time to time and creating a contineous chemical barriers and around the columns pit ,wall,trenches,top surface of plith filling junction of wall & floor along the external perimeter of the building,expansion joints over the top surface of consolidated earth of which approach is to be laid surrounding of pipes & conduits etc. complete as per specification(plinth floor area only,shall be measured for payment) (Non BSR)	1505.58	sq.m		
Total Amount Rs.					
GROUND FLOOR (ABOVE D.P.C. LEVEL)					
10	SUPER STRUCTURE MASONRY -				
(a)	115 mm Brick work with F.P.S. bricks of class designation 75 in super structure above plinth level in all shapes and sizes in : Cement mortar 1 : 4 (1 cement : 4 coarse sand) including curing & racking joints both side.	48.30	cu.m		
(b)	230mm Brick work with F.P.S. bricks of class designation 75 in super structure above plinth level in all shapes and sizes in : Cement sand mortar 1 : 6 (1 cement : 6 coarse sand) including curing & racking joints both side.	141.57	cu.m		
Total Amount Rs.					

11	SHUTTERING WORK IN COLS / BENDS IN BRICK WORK / LINTELS / BEAMS / SLAB / CHAJJA / PROJECTIONS ETC.				
(a)	Centering & shuttering with plywood or steel plates including strutting, propping bracing both ways with steel props and removal of formwork upto floor level for Columns.	221.41	sq.m		
(b)	Centering & shuttering with plywood or steel plates including strutting, propping bracing both ways with steel props and removal of formwork for :Lintels,Bends in brick work, Beams, roofs, staircases, Landings, balconies,cantilevers etc.	862.81	sq.m		
Total Amount Rs.					
12	REINFORCEMENT				
	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) complete in all respect.	17526.73	kg.		
Total Amount Rs.					
13	CEMENT CONCRETE WORK IN COLUMNS / BENDS IN BRICK WORK / LINTELS / BEAMS / SLAB				
(a)	Reinforced cement concrete work in walls & Lintels upto floor level (any thickness & size) including curing, compaction, finishing with rendering. cement sand mortar 1:1.5:3 (1 cement :1.5 coarse sand :3 graded stone aggregate 20 mm nominal size) Or M-20 Nominal mix complete in all respect.	5.34	cu.m		
(b)	Reinforced cement concrete work in columns upto floor level including curing, compaction with vibrator, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) in 1:1:2 (1 cement : 1 coarse sand: 2 graded stone aggregate 20mm nominal size) or M-25 nominal mix	27.30	cu.m		
(c)	Reinforced cement concrete work in beams ,roofs ,balconies ,chajjas ,staircases, landings including curing compaction with needle & plate vibrators,finishing with rendering in cement sand mortar 1:3(1 cement :3 coarse sand), :with 1:1.5:3 (1 cement: 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size) Or M-20 Nominal mix	115.40	cu.m		
Total Amount Rs.					
14	PLASTERING-WALLS & CEILING				
(a)	Plaster on new surface in cement sand mortar 1:4 including racking of joints etc. 12mm thick in plumb fine finish including curing. On slab & beams. Complete in all respect	477.55	sq.m		
(b)	Plaster on new surface in cement sand mortar 1:6 including racking of joints etc. 20mm thick in plumb fine finish including curing. On walls & columns. Complete in all respect.	1700.77	sq.m		
(c)	Making 50X50mm coving in all vertical / horizontal corners. Complete in all respect.(Non BSR)	488.59	r.m.		
Total Amount Rs.					
15	FLOORING & DADO				
(a)	Kota stone flooring ready size 550X550X25 mm thick laid over 35 mm (average) thick base and jointed with grey cement slurry including gridding, rubbing and granite polishing complete in all respect. (base of cement mortar 1 cement : 4 coarse sand). leaving 4x4mm groove for epoxy compound. except office & receiving bay area.	900.00	sq.m		
(b)	providing & fixing 50x50mm granite polished kota stone coving flushed with plaster & kota floor. Complete in all respect.	375.00	r.m		
(c)	Providing & Fixing premium quality double charged nano finish vitrified tiles 800X800X10mm thick on floor, skirting etc of approved make & design laid with 35 mm thick CM 1 : 4 including grouting the joints with matching tile grout complete in all respect. In office area only (NON BSR)	150.00	sq.m		

(d)	Providing and fixing premium quality ceramic glossy / mat wall tiles 300X600 of approved make & design in cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry including pointing with matching tile grout of approved make. complete in all respect.(NON BSR)	71.00	sq.m		
(e)	Providing and fixing Granite stone slab mirror polished and machine cut edge on walls, pillars, steps, Sills Counters, Floors etc. laid on 35 mm (Av.) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) jointing with white cement & pigment to match the shade of granite slab above 1500 Cm2 complete in all respect.	4.00	sq.m		
(f)	Providing & laying in the joints of Kota stone floor epoxy compound (resin, hardner & pigment) 4mm wideX10mm deep.(NON BSR)	3200	r.m		
(g)	Providing & laying M-30 grade controlled cement concrete pavements including Mixing & vibrations concrete with necessary needle vibrators and surface with screed board vibrating complete in all respect with 20/25 mm stone aggregate(crusher broken)including anti skid texture finish required camber/super elevation and grade including curing etc.as per specification with cement concreteM-30 grade including cost of steel frame workfor side of CC pavement consisting of M.S. channel flats and angles with required steel pegs (Some of them may left embedded in concrete/including frame work.150 mm thick in receiving bay area only.	27.40	cum.		
(h)	Cutting of construction joints longitudinal joints 4 to 8 mm wide using mechanical concrete cutter including cost of diamond bit cutting wheel and filling of bitumen sealing compund in groove including cost of sealing compund(75 mm depth)	336	r.m		
Total Amount Rs.					
16	FALSE CEILING & P.O.P				
(a)	Providing & fixing L / Main-at 600mm c/c / Cross-at 230mm c/c / hangers of GI sheet 24 guage covered with heavy murga jali & finished with super fine pop in water level. Complete in all respect. In office area only.(NON BSR)	140.00	sq.m		
(b)	Providing & fixing 0.5mm thick steel skin both sides 50mm thick false ceiling. Colour can be grey / white. with puff, rockwool core material ceiling panel In common passage area non conductive panel surrounded by 0.8mm gi sheet metal frame to prevent dust accumulation. panel with intermediate joint aluminium extrusion cross Tee / aluminium main grid Tee including cutout with reinforcement or lighting fixtures & air supply grill. system not capable for walking. other than office / double ht. / receiving bay area. (NON BSR)	360.00	sq.m		
(c)	Providing & applying plaster of paris over cement plaster surface in water level & plumb in all internal walls & ceiling (where no tile work & false ceiling is done) Complete in all respect. In office area only. (NON BSR)	80.00	sq.m		
Total Amount Rs.					
17	PAINTING				
(a)	Wall / Ceiling painting on cement plaster surface with washable mat finish oil paint 3 to 4 coats of approved brand and manufacture to give an even shade including all scaffolding. preparation of base with primer, putty, lippy etc complete in all respect. other than office area. (NON BSR)	1591.99	sq.m		
(b)	Wall / Ceiling painting on pop surface with acrylic paint 3 to 4 coats of approved brand and manufacture to give an even shade including all scaffolding. preparation of base with primer, putty, lippy etc complete in all respect. In office area only. (NON BSR)	220.00	sq.m		
Total Amount Rs.					
18	GMP DOORS / WINDOWS / VENTS				

(a)	Providing & fixing M.S. Powder coated doors shutters with chaukhats blue / grey white / ivory white. The core material can be puff, rock wool, polystyrene, honeycomb including tempered view glass & all hardware like hinges, handles, door stoppers, door buffers, door closers or floor machine (if required) mortice lock, auto drop door seal, ss kick plate 15mm wide X4mm thick etc. confirming to GMP norms as per drg. (NON BSR)	106.85	sq.m		
(b)	Providing & fixing M.S. powder coated windows & vents with double layer 5mm tempered glass & all hardware confirming to GMP norms as per drg. (NON BSR)	11.82	sq.m		
Total Amount Rs.					
19	ALUMINIUM DOORS / WINDOWS / VENTS				
(a)	Providing & fixing Aluminium Powder coated door shutters in 80x45mm section with chaukhats in 100x45mm ivory / white. as per drg with all hardware like hinges, handles, door stoppers, door buffers, door closers or floor machine (if required) mortice lock etc & 6mm plane glass. (NON BSR)	13.13	sq.m		
(b)	Providing & fixing Aluminium powder coated window & vent shutters in 50x25mm section with chaukhats in 100x45mm with 6mm plain glass, locking system & handles etc. complete in all respect. (NON BSR)	9.70	sq.m		
Total Amount Rs.					
FIRST FLOOR					
1	SUPER STRUCTURE MASONRY				
(a)	115 mm Brick work with F.P.S. bricks of class designation 75 in super structure in all shapes and sizes in Cement mortar 1 : 4 (1 cement : 4 coarse sand) including curing & racking of joints both side.	16.75	cu.m		
(b)	230mm Brick work with F.P.S. bricks of class designation 75 in super structure in all shapes and sizes in Cement sand mortar 1 : 6 (1 cement : 6 coarse sand) including curing & racking of joints both side.	120.52	cu.m		
Total Amount Rs.					
2	SHUTTERING WORK IN COLS / BENDS IN BRICK WORK / LINTELS / BEAMS / SLAB / CHAJJA / PROJECTIONS ETC.				
(a)	Centering & shuttering with plywood or steel plates including strutting, propping bracing both ways with steel props and removal of formwork upto floor level for :Columns.	202.44	sq.m		
(b)	Centering & shuttering with plywood or steel plates including strutting, propping bracing both ways with steel props and removal of formwork for :Lintels, bends in brick work, Beams, roofs, staircases, Landings, balconies, cantilevers etc.	845.83	sq.m		
Total Amount Rs.					
3	REINFORCEMENT				
	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) complete in all respect.	17861.68	KG		
Total Amount Rs.					
4	CEMENT CONCRETE WORK IN COLUMNS / BENDS IN BRICK WORK / LINTELS / BEAMS / SLAB				
(a)	Reinforced cement concrete work in walls & Lintels upto floor level (any thickness & size) including curing, compaction, finishing with rendering. cement sand mortar 1:1.5:3 (1 cement :1.5 coarse sand :3 graded stone aggregate 20 mm nominal size) Or M-20 Nominal mix. complete in all respect.	5.46	cu.m		

(b)	Reinforced cement concrete work in columns upto floor level including curing, compaction with vibrator, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) in 1:1:2 (1 cement : 1 coarse sand: 2 graded stone aggregate 20mm nominal size) or M-25 nominal mix	27.80	cu.m		
(c)	Reinforced cement concrete work in beams, roofs ,balconies ,chajjas, staircases, landings including curing compaction with needle & plate vibrators,finishing with rendering in cement sand mortar 1:3(1 cement :3 coarse sand), :with 1:1.5:3 (1 cement: 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size) Or M-20 Nominal mix	111.64	cu.m		
Total Amount Rs.					
5 PLASTERING -WALLS, CEILING & COVING IN CEMENT MORTAR					
(a)	Plaster on new surface in cement sand mortar 1:4 including racking of joints etc.12mm thick in plumb fine finish including curing on ceiling & beams. Complete in all respect	633.16	sq.m		
(b)	Plaster on new surface in cement sand mortar 1:6 including racking of joint etc. 20mm thick in plumb fine finish including curing on walls & pillars. Complete in all respect.	539.83	sq.m		
(c)	Making 50X50mm coving in all vertical / horizontal corners. Complete in all respect.(Non BSR)	150.00	r.m		
Total Amount Rs.					
6 FLOORING & DADO					
(a)	P & F premium quality double charged nano finish vitrified tiles 800X800X10mm thick on floor, skirting etc of approved make & design laid with 30 mm thick CM 1 : 4 including grouting the joints with matching tile grout complete in all respect. In office area only (NON BSR)	152.95	sq.m		
(b)	Providing and fixing premium quality ceramic glossy / mat wall tiles 300X600 of approved make & design in cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry including pointing with matching tile grout of approved make. complete in all respect. (NON BSR)	50.00	sq.m		
(c)	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, making of lines or groove etc complete but excluding the cost of nosing of steps etc. 40mm thick with 20mm thick nominal size aggregate.in service area only.	338.67	sq.m		
(d)	Providing and fixing Granite stone slab mirror polished and machine cut edge on walls, pillars, steps, Sills Counters, Floors etc. laid on 35 mm (Av.) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) jointing with white cement & pigment to match the shade of granite slab above 1500 Cm2 complete in all respect.	2.00	sq.m		
Total Amount Rs.					
7 FALSE CEILING & P.O.P.					
(a)	Providing & fixing 0.5mm thick steel skin both sides 50mm thick false ceiling. Colour can be grey / white. with puff, rockwool core material ceiling panel In common passage area non conductive panel surrounded by 0.8mm gi sheet metal frame to prevent dust accumulation. panel with intermediate joint aluminium extrusion cross Tee / aluminium main grid Tee including cutout with reinforcement or lighting fixtures & air supply grill. system not capable for walking. other than office / double ht. / receiving bay area. (NON BSR)	525.00	sq.m		
(b)	Providing & fixing L / Main-at 600mm c/c / Cross-at 230mm c/c / hangers of GI sheet 24 guage covered with heavy murga jali & finished with super fine pop in water level. Complete in all respect. In office area only.(NON BSR)	153.00	sq.m		

(c)	Providing & applying plaster of paris over cement plaster surface in water level & plumb in all internal walls & ceiling (where no tile work is done) Complete in all respect. In office area only.	350.00	sq.m		
Total Amount Rs.					
8 PAINTING					
(a)	Wall / ceiling painting on cement plaster surface with washable mat finished oil paint 3 to 4 coats of approved brand and manufacture to give an even shade including all scaffolding. preparation of base with primer, putty, lippy etc complete in all respect. other than office area. (NON BSR)	589.39	sq.m		
(b)	Wall / Ceiling painting on pop surface with acrylic paint 3 to 4 coats of approved brand and manufacture to give an even shade including all scaffolding. preparation of base with primer, putty, lippy etc complete in all respect. In office area only. (NON BSR)	500.00	sq.m		
Total Amount Rs.					
9 GMP DOORS / WINDOWS / VENTS					
(a)	Providing & fixing M.S. Powder coated doors shutters with chaukhats blue / grey white / ivory white. The core material can be puff, rock wool, polystyrene, honeycomb including tempered view glass & all hardware like hinges, handles, door stoppers, door buffers, door closers or floor machine (if required) mortice lock etc. confirming to GMP norms as per drg. (NON BSR)	4.20	sq.m		
(b)	Providing & fixing M.S. powder coated windows & vents with double layer 5mm tempered glass & all hardware confirming to GMP norms as per drg. (NON BSR)	28.10	sq.m		
Total Amount Rs.					
10 ALUMINIUM DOORS / WINDOWS / VENTS					
(a)	Providing & fixing Aluminium Powder coated door shutters in 80x45mm section with chaukhats in 100x45mm ivory / white. as per drg with all hardware like hinges, handles, door stoppers, door buffers, door closers or floor machine (if required) mortice lock etc & 6mm plane glass. (NON BSR)	24.15	sq.m		
(b)	Providing & fixing Aluminium powder coated window & vent shutters in 50x25mm section with chaukhats in 100x45mm with 6mm plain glass, locking system & handles etc. complete in all respect. (NON BSR)	21.67	sq.m		
Total Amount Rs.					
TERRACE FLOOR					
1 BRICK WORK IN PARAPET WALL					
	230mm Brick work with F.P.S. bricks of class designation 75 in superstructure in all shapes and sizes in : Cement sand mortar 1 : 6 (1 cement : 6 coarse sand) including curing & racking joints both sides	18.84	cu.m		
Total Amount Rs.					
2 TAPER CHAJJAS & DESIGN WORK					
	Making taper chajjas & cement design work as per existing building. (NON BSR)	89.50	sq.m		
Total Amount Rs.					
3 C.C. PILLARS & CEMENT JALI					
	Providing, hoisting & fixing precast cement concrete Jali 1:2:4,(1-cement ,2-sand,& 4-coarse aggergate-6 mm nominal size)reinforced with 1.6 mm dia. Mild steel wire including centering,& shuttering ,roughening ,cleaning,fixing & finishing in cement mortar 1:3(1-cement,3-fine sand)etc. complete as per approved design excluding plastering of jamb,sills & soffits.50 mm thick	26.60	sq.m		

	Total Amount Rs.				
4	GRADING COURSE				
	Providing & Laying cement concrete including curing, compaction etc. complete on slab with 1:1.5:3/M-20, (1 cement ; 1.5 sand ; 3 coarse aggregate) as grading (Average thickness 75 mm)	39.00	cu.m		
	Total Amount Rs.				
5	MOSAIC TILES				
	Providing & Fixing branded & approved make 1st quality 250x250mm mosaic tiles in grey cement laid over 35mm thick (av) bed in 1:4 cement mortar with griding & ordinary polishing. Complete in all respect.	511.42	sq.m		
	Total Amount Rs.				
6	WATER PROOFING				
	<p>Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying :</p> <p>a) after surface preparation, first layer of slurry of cement @ 0.488 kg/sqm mixed with water proffing cement compound @ 0.253 kg/sqm.</p> <p>b) laying second layer of Fiber glass cloth when the first layer is still green . Overlaps of joints of fiber cloth should not be less than 10 cm .</p> <p>c) Third layer of 1.5 mm thickness consisting of slurry of cement @ 1.289 kg/sqm mixed with water proffing cement compound @ 0.670 kg/sqm and coarse sand @ 1.289 kg/sqm. This will be allowed to air cure for 4 hours followed by water curing for 48 hours. The entire treatment will be taken upto 30cm on parapet wall and tucked into groove in parapet all around</p> <p>d) fourth and final layer of brick tiling with cement mortar or any other approved protective coarse. (which will be paid for separately) For the purpose of measurement the entire treated surface will be measured</p>	511.42	sq.m		
	Total Amount Rs.				
7	PLASTER INSIDE PARAPET WALLS				
	Plaster on new surface of walls in cement sand mortar 1:6 including racking of joint etc. 20mm thick fine finish including curing. Complete in all respect.	227.64	sq.m		
	Total Amount Rs.				
8	EXTERNAL PLASTER				
	External Plaster on new surface of walls in cement sand mortar 1:4 including racking of joints etc. 20mm thick fine finish including curing. Complete in all respect	1089.82	sq.m		
	Total Amount Rs.				
9	EXPANSION JOINT				
	Supplying & providing of two components poly sulphide sealent containing solid contents, confirming to standard specification & approved compatible primer, for priming vertical faces prior to application of poly sulphide sealent including all labour charges for sealing of expansion joints after drill mixing of two components sealing compound. Cleaning & preparation of expansion joints using wire brush sand papering with emery paper & filling with suitable mechanical means. The work includes racking & cleaning of joints, sticking, debonding tape on bottom of joint, apply primer on edge, proving of sealent & removal of masking tape immediately after providing sealent in Joints. To vertical joints between RCC column, brick & stone masonry in size 40 mm width and 12 mm depth, including providing back up material (Thermocol foam) if required	32.00	r.m		
	Total Amount Rs.				

10	EXTERIOR PAINT ACE / APEX / WEATHER SHIELD				
	Wall painting with approved brand and manufacture to give an even shade including all scaffolding. 3 to 4 coats on new work including preparation of base with 2 coats of birla putty, primer, lippy etc complete in all respect. (NON BSR)	1143.01	sq.m		
	Total Amount Rs.				
11	MATELLIC ARCHED ROOF				
	Providing & fixing colour coated aluminium-zink alloy sheet (galvalume) of ASTM - A792, grade D, coating - AZ150 thickness BMT 0.90mm TCT 0.97mm including all hangers, fastners. Complete in all respect. (NON BSR)	597.00	sq.m		
	Total Amount Rs.				
12	TIN ROOFING / OTHER IRON WORK / ACP FALSE CEILING				
a	Providing & fixing pre-colour coated aluminium-zink alloy sheet ,having yield strenth of 240 Mpa,galvanizing in accoradance with IS: 277/JIS:3302, Zinc coating -120 GSM(Both sides mass),pre-painted as per the IS:14246/JIS:3312,having thickness of 0.50/0.60 mm Including all hangers, fastners,J-botls & etc.. Complete in all respect.(Non BSR)	218.95	sq.m		
b	Iron structure to support coloured zinc sheet. Iron structure for staircase / platform / saftey grills in receiving bay area.	5000	kg		
c	Providing & Fixing 35X35mm hollow iron pipes frame work at 1200X1200mm c/c finished with 4mm thick exterior grade Acp sheets false ceiling.	218.95	sq.m		
	Total Amount Rs.				
13	AIR CONDITIONING				
a	Providing / fixing & making jhiri in brick wall / cement concrete for 15mm & 6mm copper pipe with 12mm thick insulation along with 20mm cpvc drain pipe & 4 core 2.5sq mm electric cable for 1.5 ton to 2.0 ton AC units. (NON BSR).	200.00	r.m		
b	Providing / fixing & making jhiri in brick wall / cement concrete for 18mm & 9mm copper pipe with 20mm thick insulation along with 25mm cpvc drain pipe & 4 core 2.5sq mm electric cable for 2.5 ton to 3.0 ton AC units. (NON BSR).	30.00	r.m		
	Total Amount Rs.				
GRAND TOTAL					