

Bill of Quantities
EXTRA ITEMS IN EXISTING BUILDING R.D.P.L. ROAD NO. 12, V.K.I.A. JAIPUR

NO	ITEM	QUANTITY	UNIT	RATE	AMOUNT
1	REMOVING ALL EXISTING PAINT/MAKING EXISTING PLASTER SURFACE ROUGH BY MAKING DEEP CUT AT 1" INTERVAL & DOING SUPER FINE POP IN PLUMB INCLUDING COST OF POP MATERIAL	600	Sq.m		
2	PROVIDING & FIXING GRANITE 4' TO 4'-6" HIGH IN SINGLE PIECE PROJECTING 6MM FROM FINISHED WALL SURFACE VERTICAL JOINTS AT 2' TO 2'-6" DISTANCE AS PER SLAB WIDTH AVAILABLE FILLED WITH MATCHING EPOXY COMPOUND AFTER TAKING OUT THE EXISTING PLASTER INCLUDING COST OF ALL MATERIALS.	525	Sq.m		
3	MAKING 4MM X 10MM GROOVE IN EXISTING KOTA STONE FLOORING & TO BE FILLED WITH MATCHING EPOXY COMPOUND INCLUDING COST OF EPOXY COMPOUND	500	R.m		
4	WALL/ CEILING PAINTING ON POP SURFACE WITH WASHABLE MAT FINISH OIL PAINT 3 TO 4 COATS OF APPROVED BRAND & MANUFACTURE TO GIVEN AN EVEN SHADE INCLUDING ALL SCAFFOLDING PREPARTION OF BASE WITH PRIMER, PUTTY, LIPPY ETC. COMPLETE IN ALL RESPECT.	600	Sq.m		
5	PROVIDING & FIXING 50X50MM GRANITE POLISHED KOTA STONE COVING WITH 100MM SKIRTING FLUSHED WITH PLASTER & KOTA FLOOR. COMPLETE IN ALL RESPECT. INCLUDING COST OF ALL MATERIALS	500	R.m		
6	ONLY FIXING OF IRON POWDER COATED GMP DOORS & WINDOWS	75	Sq.m		
7	PROVIDING & FIXING 50X4MM THICK IRON PLATE POWDER COATED IN SAME EXISTING COLOUR OVER EXISTING DOORS & WINDOWS TO COVER THE JOINT OF PLASTER & DOOR/WINDOW FRAME.	1500	R.m		
8	PROVIDING & DOING ELECTRIC WIRING OF LIGHTING FIXTURES IN VARIOUS SECTIONS ONLY LIGHT FIXTURES TO BE PROVIDED BY R.D.P.L.	150	Per		
	TOTAL				