

Bill of Quantities**EXTRA ITEMS IN EXISTING BUILDING R.D.P.L. ROAD NO. 12, V.K.I.A. JAIPUR**

NO	ITEM	QUANTITY	UNIT	RATE	AMOUNT
1	REMOVING ALL EXISTING PAINT/MAKING EXISTING PLASTER SURFACE ROUGH BY MAKING DEEP CUT AT 1" INTERVAL & DOING SUPER FINE POP IN PLUMB INCLUDING COST OF POP MATERIAL	600	Sq.m		
2	PROVIDING & FIXING GRANITE 4' TO 4'-6" HIGH IN SINGLE PIECE PROJECTING 6MM FROM FINISHED WALL SURFACE VERTICAL JOINTS AT 2' TO 2'-6" DISTANCE AS PER SLAB WIDTH AVAILABLE FILLED WITH MATCHING EPOXY COMPOUND AFTER TAKING OUT THE EXISTING PLASTER INCLUDING COST OF ALL MATERIALS.	525	Sq.m		
3	MAKING 4MM X 10MM GROOVE IN EXISTING KOTA STONE FLOORING & TO BE FILLED WITH MATCHING EPOXY COMPOUND INCLUDING COST OF EPOXY COMPOUND	500	R.m		
4	WALL/ CEILING PAINTING ON POP SURFACE WITH WASHABLE MAT FINISH OIL PAINT 3 TO 4 COATS OF APPROVED BRAND & MANUFACTURE TO GIVEN AN EVEN SHADE INCLUDING ALL SCAFFOLDING PREPARATION OF BASE WITH PRIMER, PUTTY, LIPPY ETC. COMPLETE IN ALL RESPECT.	600	Sq.m		
5	PROVIDING & FIXING 50X50MM GRANITE POLISHED KOTA STONE COVING WITH 100MM SKIRTING FLUSHED WITH PLASTER & KOTA FLOOR. COMPLETE IN ALL RESPECT. INCLUDING COST OF ALL MATERIALS	500	R.m		
6	ONLY FIXING OF IRON POWDER COATED GMP DOORS & WINDOWS	75	Sq.m		
7	PROVIDING & FIXING 50X4MM THICK IRON PLATE POWDER COATED IN SAME EXISTING COLOUR OVER EXISTING DOORS & WINDOWS TO COVER THE JOINT OF PLASTER & DOOR/WINDOW FRAME.	1500	R.m		
8	PROVIDING & DOING ELECTRIC WIRING OF LIGHTING FIXTURES IN VARIOUS SECTIONS ONLY LIGHT FIXTURES TO BE PROVIDED BY R.D.P.L.	150	Per		
9	FALSE CEILING				
	Providing & fixing 0.5mm thick steel skin both sides 50mm thick false ceiling. Colour can be grey / white. with puff, rockwool core material ceiling panel In common passage area non conductive panel surrounded by 0.8mm gi sheet metal frame to prevent dust	90.76	sq.m		
10	GMP DOORS				
	Providing & fixing Powder coated doors shutters with chaukhats blue / grey white / ivory white. with 20 SWG GI sheet 38±2 kg/m ² . The core material can be puff, rock wool of suitable density including tempered view glass & all hardware like hinges, handles,	38.00	sq.m		

11	PARTITION				
	Providing & Fixing powder coated partitions using 1½"X1¼" aluminium section at 2'X4' interval with 20 SWG GI 38±2 kg/m2 including puff filling /rockwool of suitable density flushed on both sides & view panels of standard size. Complete in all respect & a	58.74	sq.m		
12	GMP DOORS				
	Providing & fixing Powder coated doors shutters with chaukhats blue / grey white / ivory white.with 20 SWG GI sheet 38±2 kg/m2. The core material can be puff, rock wool of suitable density including tempered view glass & all hardware like hinges, handles,				
	(a) Material air lock 1.0X2.1m (6 nos)	12.60	sq.m		
	(b) Material air lock 1.5X2.1m (2 nos)	6.30	sq.m		
	(a) Person air lock 1.2X2.1m (24 nos)	60.48	sq.m		
	(b) Person air lock 1.0X2.1m (10 nos)	21.00	sq.m		
13	PARTITIONS				
	Providing & Fixing powder coated partitions using 1½"X1¼" aluminium section at 2'X4' interval with 20 SWG GI 38±2 kg/m2 including puff filling /rockwool of suitable density flushed on both sides.& view panels of standard size.Complete in all respect & as				
	2.0X3.0M (21 NOS)	126.00	sq.m		
14	FALSE CEILING				
	Providing & fixing 0.5mm thick steel skin both sides 50mm thick false ceiling. Colour can be grey / white. with puff, rockwool core material ceiling panel In common passage area non conductive panel surrounded by 0.8mm gi sheet metal frame to prevent dust	75.64	sq.m		
15	PROVIDING & FIXING PASS BOXES OF				
	(a) 1.0X0.9m	6.00	Nos.		
	(b) 1.2X0.9m	6.00	Nos.		
	(c) 1.5X0.9m	2.00	Nos.		
	(d) 1.68X0.9m	6.00	Nos.		
	TOTAL				